TOWN MUNICIPAL OFFICE, ARSIKERE.

Notice dated 12th November 1928.

Notice is hereby given that sealed tenders will be received at the Office of the President, Municipal Council, Arsikere, up to 30th November 1928, for the construction of works noted below in Arsikere Town. An approximate estimate of quantities is given below. The quantities are not guaranteed. The work should be completed by the end of June 1929.

2. The plans, detailed estimate and conditions may be seen at the Office of the President, during office hours.

3. Tenders should be submitted in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 100 for each of the works in cash or Government Promissory Notes, as earnest money, and be superscribed "Tenders for the construction of (1) street drain in Kadlipet, (2) street drain to Mosque Street, (3) slaughterhouse and (4) repairs to Ullibhavi."

5. The final acceptance of any tender will rest with the President, Municipal Council, Arsikere, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within five days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Municipal Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. The rate should be noted both in figures and in words in the form without any corrections or additions.

10. No claim for any higher rate on any account will be entertained after the tender is accepted

11. Tenders at percentage above or below the estimate rates or below the lowest tender will not be accepted.

12. The contractor will be dealt with in terms of his bond for any short progress or delay.

13. In the matters of all disputes about rates and measurements, quantity or work, etc., and in all disputes of any kind, the decision of the President will be final and legally binding.

14. Charges on account of implements for setting out, barricading, cleaning site, supply of water, etc., that may be found necessary during execution will not be paid for separately, but should be borne entirely by the contractor.

Approximate quantity of works for the construction of Slaughterhouse in Arsikere Town.

No.	Items of work	Per	Quantity	Tenders rate
				Rs. a. p.
1	Earthwork excavation in ordinary soil ...	C.yd.	24	
2	Jelly concrete in chunam mortar	C.ft.	401	
3	Jelly concrete in cement mortar	,,	55	
4	Burnt size stone in mortar	,,	383	
5	Burnt brick in mortar	,,	877	
6	Burnt stone slabs 6" thick dressed and put up ...	S.ft.	65	
7	Do dressed on all sides for pillar ...	,,	12	
8	Honne, nandi or mathi wood work wrought and put up.	C.ft.	41	
9	Teakwood door with frame and pannelled shutters and 1 ft. wire gauge frame at the bottom, complete.	S.ft.	23	
10	Teakwood door with frame and pannelled shutters, complete.	,,	36	
11	Teakwood windows with frame, iron bars, pannelled shutter outside and wire gauge netting inside.	,,	40½	
12	Teakwood gate door	,,	12	
13	Roofing with First Class Mangalore tiles on teak reepers.	Sqrs.	6·33	

No.	Items of work	Per	Quantity	Tenders rate
14	Ridge tiles set in mortar	R.ft.	38 3/8	
15	Chunam bordering	,,	33	
16	Coping with burnt brick in mortar	,,	62	
17	Filling in basement with earth and tamping ...	C.yd.	15	
18	Flooring with Cudhapah slab on 3" concrete including cement pointing the joints.	Sqr.	5·88	
19	Plastering with mortar	,,	15·00	
20	White washing two coats	,,	15·00	
21	Cement plastering ½" thick 1 : 3 proportion ...	,,	5·07	
22	Cement pointing	,,	1·39	
23	One inch diameter iron rod	lbs.	62	
24	Iron hooks on 3 feet iron rod of ½" diameter ...	Each	12	
25	T. iron posts of 2" flanges with bottom plate ...	lbs.	168	
26	Wire fencing	100 R.ft.	185	
27	Tarring the wood	Sqr.	4·00	
28	Chocolate painting	,,	2·36	

Approximate quantity of works for the repairs of Ullibhavi in the Arsikere Town.

No.	Items of work	Per	Quantity	Tender rate
1	Removing the silt and the fallen stones in the pond	Lump sum		Rs. a. p.
2	Earthwork excavation	C.yd.	292	
3	Removing and rebuilding the revetment with the available stones.	,,	434	
4	Fresh revetment work in case the existing rubble stones are found insufficient for the completion of the work.	,.	200	
5	Burnt stone in mortar for toe wall ...	C.ft.	1,403	
6	Cement pointing	Sqr.	7.92	

Approximate quantity of works for the construction of Street Drain in Kadlipet of Arsikere Town.

No.	Items of work	Per	Quantity	Tenders rate
	3" Silk Pattern Drain.			Rs. a. p.
1	Earthwork excavation in ordinary soil ...	C.yd.	19	
2	Jelly concrete in surki mortar	C.ft.	669	
3	Fresh burnt stone slabs 3" to 4" thick dressed on the top side including cement pointing the joints.	S.ft.	1,824	
4	Cement plastering ½" thick	Sq.	18	
5	Gravel backing to sides	C.yd.	120	

Approximate quantity of works for the construction of street drain in Mosque Srteet in Arsikere Town.

	3" Silk Pattern Drain.			Rs. a. p.
1	Earthwork excavation in ordinary soil ...	C.yd.	21	
2	Jelly concrete in surki mortar	C.ft	770	
3	Fresh burnt stone slabs 3" to 4" thick dressed on the top side, including cement pointing the joints.	S.ft.	2,100	
4	Cement plastering ½" thick	Sqr.	20	
5	Gravel backing to sides	C.yd.	124	

M. RAMAIYA,
President, Town Municipal Council,
Arsikere.